

Reviewing Pool Plans

Basic Swimming Pool Plan Review and
Pipe Calculations Training



Items You Will Need

- Pool Plans and Equipment Specifications
- Pool Rules – Office Administrative Hearings Website

<http://reports.oah.state.nc.us/ncac.asp?folderName=%5CTitle%2015A%20-%20Environmental%20Quality%5CChapter%2018%20-%20Environmental%20Health>

- Calculator and Architect's Scale
- Flow Chart for Schedule 40 Pipe – Velocity
- Highlighters (3 or 4 different colors)
- NSF.org



Items You Will Need

- Pool Plan Review Checklist
- Drain safety data sheet
- Plan review calculations sheet



What Should Plans Include?

- Rule .2509 states the plans shall be prepared by a “registered design professional”, which is either a:
 - NC Professional Engineer (P.E.), or a
 - NC Registered Architect
- Two complete sets of plans shall be submitted
 - Minimum size (18 x 24 inches)
 - Maximum size (36 x 42 inches)
 - Plans shall be drawn to scale
 - Plans shall include specifications



Quiz time?

- What about landscape Architects?



What Should Plans Include?

1. Plan and sectional view dimensions of both the pool and the area enclosed by the barrier fences to include the bathhouse and the equipment room and pool accessories
2. Specifications of all treatment equipment used and their layout in the equipment room
3. A piping schematic showing piping, pipe size, inlets, main drains, skimmers, gutter outlets, vacuum fittings and all other appurtenances connected to the pool-piping system



What Should Plans Include?

4. Layout of the chemical storage room
5. Specifications for the water supply and wastewater disposal systems that include aspects such as well location and backwash water disposal where applicable.



Pool Plan Review Deadline

- The Department shall approve, disapprove, or provide written comments on plans and specifications for public swimming pools **within 30 days of their receipt.**

*If such action is not taken within 30 days, the plans and specifications shall be deemed approved.



What To Do First?

- Complete the Drain Safety Data Sheet first.
- Next, complete the calculations sheet.
- Finish with the Pool Plan Review Checklist – Look for each of the checklist items on the plans. Determine if the items meet the rules.
- If items don't meet the rules – they will need to be addressed in the letter to the engineer or architect.



What To Do Next?

- If some specifications are not included, try to complete as much of the checklist as possible, list missing items for letter.
- Contact the engineer or architect to send the necessary specifications.
- If specifications can't be obtained quickly – send a disapproval letter indicating the specifications that are needed to complete the plan review.



Reviewing the Plans

- Once you have completed the calculations and checklist, you have the information that you need to write an approval or a disapproval letter. Items you have “flagged” will be the items you list in your letter.
- In some cases, you may have only minor items flagged that can be communicated as conditions in an approval letter. (You can also include reminders.)



Important Things to Remember

- There have been some changes in the rules since 2010 that you need to be aware of when reviewing plans.
 - Open-pipe inspection - .2509(e)
 - Pool finish (use artist gray scale or reflectance testing to determine if finish is light enough) - .2514 (c)
 - Sun shelves - .2515 (b) – connect to pool with stairs or properly sloped floor.
 - Skimmer piping (after 5/1/2010) shall be sized to handle the maximum flow rate for the required number of skimmers, but in no case less than 100 percent of the design flow rate - .2518 (c)



Important Things to Remember

- Perimeter overflow system piping (after 5/1/2010) shall be sized to handle 100 percent of the design flow rate. - .2518 (c)
- The main drain piping (after 5/1/2010) shall be sized to handle 100 percent of the design flow rate. - .2518 (c)
- Vacuum ports that are provided shall be at least 6 inches and no greater than 18 inches below the water line and shall have a self-closing cap designed to be opened with a tool. - .2518 (f)




Important Things to Remember

- Flow-through rate for each skimmer is between 20 gpm and the maximum flow the skimmer is certified for under NSF Standard 50. - .2518(k)(3)(A)
- For stairs wider than 20 feet, additional handrails shall be provided and spaced no more than 10 feet from adjacent handrails or stair ends. - .2521 (b)(3)
- Lighting – Must meet .2524 (d or e) for new pools
- Fences – 45 inches between horizontal members and no more than 2 inches underneath. .2528



Important Things to Remember

- Drain Safety Compliance in Rule .2539 SUCTION HAZARD REDUCTION.
- Drain Safety Data Sheet should be completed as part of plan review. You can ask RDP to include, but it is not required.





Turnover Rate vs. Design Flow

- Turnover Rate – The minimum flow rate for the type of pool to meet the rule requirements.
- Design Flow Rate – Flow rate for the specific pump chosen. Measured at 65 TDH unless calculated by engineer.



Turnover Rate vs. Design Flow

The design flow rate must be greater than the minimum turnover rate to assure proper filtration and disinfection.


Design flow rate will be used for:

- Pipe sizes (will be based on 140 gpm)
- The filter(s) (must be able to filter water at 140 gpm)
- Minimum number of inlets



Also look at maximum pump flow

- Maximum Pump Flow is the amount of water the pump will pump at the lowest head shown on the pump curve.
- The maximum pump flow is used for drain cover sizing only.
- Example: If the maximum pump flow is 220 gpm – then each drain cover on a 2-drain pool shall be rated to handle a flow of at least 220 gpm or more.



Let's look at "Fairfield Inn or pool plans scan" AND a copy of the "plan review calculations and components sheet" from the items that were shared with you prior to the class.

Plan Review Group Exercise

1. **Pool type** and required turnover rate denominator.

pool use 360 ✓


First determine what type of public pool plans have been submitted and refer to the chart on the right to determine minimum turnover rate

Swimming pool with a 6-hr turnover rate:

60 min/~~1 hr~~ X ~~6 hr~~ = 360 minutes

Pool Type and Turnover Rates
6 Hour Turnover USE (360) <ul style="list-style-type: none"> Swimming pool (standing water 0+' but usually 3' min water depth) .2518(b), Water slide landing pool >60,000 gal .2543(b), Scuba pool, .2544©(2)
3 Hour Turnover USE (180) <ul style="list-style-type: none"> Water slide landing pool <60,000 gal with auto chemical controller .2543(b)
2 Hour Turnover USE (120) <ul style="list-style-type: none"> Wading pool (24" max depth separate from larger pool).2531(a)(3), Water slide pools <60,000 gal without auto chemical controller .2543(b), Training pools (24-36" depth) .2543©(1), Exercise therapy spa >1000 gal .2544(d)(2)
1 Hour Turnover USE (60) <ul style="list-style-type: none"> Stand- alone children's activity pool(CAP) .2531(b)(2)
.5 Hour Turnover USE (30) <ul style="list-style-type: none"> Recreational spas, all swim spas, hot tubs .2532(1), Interactive Play Attractions (IAPA), Spray grounds .2543(d)(5), Exercise therapy spa <1000 gal .2544(d)(2) Float Tank .2544(b)(4) 2X every hr. not in use and 2X between @ user

Page SP-1 show a 3' to 5' deep pool




POOL SPECIFICATIONS


POOL SECTION

A/E: 1/4" = 1'-0"

- WATER SURFACE AREA IS 346 SQ. FT.
- WATER DEPTH IS 3'-0" TO 5'-0"
- NET CAPACITY IS 10,366 GALLONS WITH A FILTRATION CYCLE OF 5 HOURS AND 24 MIN AT A FLOW OF 32 GPM. (BASED ON A DYNAMIC HEAD OF 65 FEET)
- POOL PERIMETER = 74.5 LN. FT
- ALL PIPE WORK SHALL BE SCHEDULE 40 PVC, PRESSURE TESTED BEFORE PLACING CONCRETE
- BATHER LOAD IS 23 PERSONS AS PER GS 15A:18A SECTION 2529
- DECK AREA = 1,787 SQ. FT. BY OTHER THAN SPC

2. Pool Perimeter (lengths + widths)





2. **Pool perimeter** (lengths + widths)
(circle perimeter = πd)

Pool Specifications on plans show 74.5 LF.
Use this number since it was calculated by a
CAD program and accounts for curved corners.



POOL SPECIFICATIONS

- WATER SURFACE AREA IS 346 SQ. FT.
- WATER DEPTH IS 3'-0" TO 5'-0"
- NET CAPACITY IS 10,366 GALLONS WITH A FILTRATION CYCLE OF 5 HOURS AND 24 MIN AT A FLOW OF 32 GPM. (BASED ON A DYNAMIC HEAD OF 65 FEET)
- POOL PERIMETER = 74.5 LN. FT ✓
- ALL PIPE WORK SHALL BE SCHEDULE 40 PVC, PRESSURE TESTED BEFORE PLACING CONCRETE
- BATHER LOAD IS 23 PERSONS
AS PER GS 15A:18A SECTION 2529
- DECK AREA = 1,787 SQ. FT. BY OTHER THAN SPC

Found on page SP1

3. Pool surface area (length X width)

Multiply length X the width


$$14' \times 25' = 350 \text{ SQ. FT.}$$

Pool Specifications on page SP-1 show **346 SQ. FT.**

POOL SPECIFICATIONS

- WATER SURFACE AREA IS 346 SQ. FT. ✓
- WATER DEPTH IS 3'-0" TO 5'-0"
- NET CAPACITY IS 10,366 GALLONS WITH A FILTRATION CYCLE OF 5 HOURS AND 24 MIN AT A FLOW OF 32 GPM. (BASED ON A DYNAMIC HEAD OF 65 FEET)
- POOL PERIMETER = 74.5 LN. FT
- ALL PIPE WORK SHALL BE SCHEDULE 40 PVC, PRESSURE TESTED BEFORE PLACING CONCRETE
- BATHER LOAD IS 23 PERSONS
AS PER GS 15A:18A SECTION 2529
- DECK AREA = 1,787 SQ. FT. BY OTHER THAN SPC

4. Pool Volume





4. **Pool volume** = length X width X avg. depth X 7.48,
(There are 7.48 gallons per cubic foot of water.)

(circular is πr^2 X avg depth X 7.48 is used for round pools.)

Length = **25'** Width = **14'** Average depth (3' + 5') = 8'/2 = **4'**

$$\mathbf{25' \times 14' \times 4' \times 7.48 = 10,472 \text{ gal}}$$

Pool Specifications on plans show 10,366 gal

POOL SPECIFICATIONS

- WATER SURFACE AREA IS 346 SQ. FT.
- WATER DEPTH IS 3'-0" TO 5'-0"
- -NET CAPACITY IS 10,366 GALLONS WITH A FILTRATION CYCLE OF 5 HOURS AND 24 MIN AT A FLOW OF 32 GPM. (BASED ON A DYNAMIC HEAD OF 65 FEET) ✓
- POOL PERIMETER = 74.5 LN. FT
- ALL PIPE WORK SHALL BE SCHEDULE 40 PVC, PRESSURE TESTED BEFORE PLACING CONCRETE
- BATHER LOAD IS 23 PERSONS
AS PER GS 15A:18A SECTION 2529
- DECK AREA = 1,787 SQ. FT. BY OTHER THAN SPC

Found on page SP1



5. **Minimum turnover flow rate** for a pool required by the rules:
pool volume (Ref #4) ÷ assigned denominator in chart (Ref #1),

10,366 gallons ÷ 360 minutes = 28.8 GPM





6. **Design flow rate** of circulation must be > than minimum turnover flow rate: Ref #6 > Ref #5


Pump Mfg; Pentair
Model #: WFE-2 HP 1/2
30 - 32 GPM at 65 TDH

Pool Specifications on page SP-1 shows
32 GPM @ 5hrs 24min

32 GPM exceeds the minimum turnover of 28 GPM



Performance Curves



POOL SPECIFICATIONS

- WATER SURFACE AREA IS 346 SQ. FT.
- WATER DEPTH IS 3'-0" TO 5'-0"
- NET CAPACITY IS 10,366 GALLONS WITH A FILTRATION
→ CYCLE OF 5 HOURS AND 24 MIN AT A FLOW OF 32 GPM.
(BASED ON A DYNAMIC HEAD OF 65 FEET)
- POOL PERIMETER = 74.5 LN. FT
- ALL PIPE WORK SHALL BE SCHEDULE 40 PVC, PRESSURE
TESTED BEFORE PLACING CONCRETE
- BATHER LOAD IS 23 PERSONS
AS PER GS 15A:18A SECTION 2529
- DECK AREA = 1,787 SQ. FT. BY OTHER THAN SPC



Design flow rate (32 gpm) will be used for:

- **Checking pipe sizes**
- **Checking filter(s) capable of handling 32 gpm**
- **Required number of inlets**



Max Flow of Circulation Pump is used for approving the drain cover

Max Flow ____**90**____ GPM

- Note: Use least resistance: lowest Total Dynamic Head. If a multi-speed or variable speed pump is provided, you must use Max flow of the highest speed for drain cover comparison and approval.



7. Number of inlets required _____, Plan shows _____
(Design flow in Ref #6 ÷ 20 GPM),

Inlet Notes:

- Must have a minimum of 4 inlets for pools and uniform circulation/ no part of pool more than 25 feet from any inlet
- Must be adjustable

Inlet Mfg. & Model #: Hayward SP-1419C


32gpm/20 = 1.6 inlets; however, are there 4 inlets to meet minimum required by the rules?




The Pool Equipment List and SP1 show 4 inlets

Inlets listed on page SP2 under equipment list

POOL EQUIPMENT LIST				
QTY.	ITEM	MANUFACTURER	MODEL #	DESCRIPTION
1	PUMP	PENTAIR	WFE-2	1/2 HP WHISPER FLO COMMERCIAL PUMP (1 PHASE PUMP)
1	BASKET	PENTAIR	070387	EXTRA STAINER BASKET
1	FILTER	PENTAIR	TR50	NSF APPROVED WITH AIR RELIEF PRESSURE GAUGE
1	VALVE	PENTAIR	261055	MULTIPORT VALVE
1	FLOWMETER	FLOW VIS	FV-C	2" PVC MOUNT (BACKWASH NOT TO EXCEED 50 GPM)
1	CHLORINATOR	PENTAIR	320	AUTOMATIC EROSION TYPE (PENTAIR #171096)
1	SKIMMER	AQUASTAR	SKR101	INCLUDES BASKET
4	RETURN INLETS	HAYWARD	SP-1419C	ADJUSTABLE EYEBALLS
2	SUCTION OUTLET	ASA	FPK-50-809	9x9 SUCTION OUTLET WITH 3" PORT
2	*MAIN DRAIN COVERS	*AQUASTAR	914101	9x9 ANTI-ENTRAPMENT FRAME & GRATE COVER (394 GPM MAX. RATING)
1	RELIEF VALVE	HAYWARD	SP-1056	1 1/2" HYDROSTATIC RELIEF VALVE
1	COLLECTOR TUBE	HAYWARD	SP-1055	1-1/2" x 12" COLLECTOR TUBE
1	AUTO FILL	PENTAIR	T40FW	AUTOFILL W/ BRASS FLOAT VALVE
1	HANDRAIL	S.R. SMITH	3HR-4-065	4'-0" STAINLESS STEEL HANDRAIL
1	LADDER	S.R. SMITH	VLLS-103S-MG	3-STEP LADDER
1	LIGHT	PENTAIR	78458100	500W INCANDESCENT UNDERWATER LIGHT (50 FT CORD)
1	NICHE	PENTAIR	78210600	STAINLESS STEEL W/ 1" HUB
1	LIFT	AQUA CREEK	RANGER	ADA COMPLIANT HANDICAP SWIM LIFT BATTERY POWERED 350 LB. OPERATING LOAD CAPACITY

*MAIN DRAINS MUST CONFORM TO ANSI/ASME A112.19.8-2007



LEGEND	
	RETURN
	SKIMMER
	MAIN DRAIN

4
SP1 POOL PLUMBING PLAN
SCALE: 1/4" = 1'-0"

**4 return inlets
shown on SP1**

8. What filter is shown on equipment list?

POOL EQUIPMENT LIST				
QTY.	ITEM	MANUFACTURER	MODEL #	DESCRIPTION
1	PUMP	PENTAIR	WFE-2	1/2 HP WHISPER FLO COMMERCIAL PUMP (1 PHASE PUMP)
1	BASKET	PENTAIR	070387	EXTRA STAINER BASKET
1	FILTER	PENTAIR	TR50	NSF APPROVED WITH AIR RELIEF PRESSURE GAUGE
1	VALVE	PENTAIR	261055	MULTIPORT VALVE
1	FLOWMETER	FLOW VIS	FV-C	2" PVC MOUNT (BACKWASH NOT TO EXCEED 50 GPM)
1	CHLORINATOR	PENTAIR	320	AUTOMATIC EROSION TYPE (PENTAIR #171096)
1	SKIMMER	AQUASTAR	SKR101	INCLUDES BASKET
4	RETURN INLETS	HAYWARD	SP-1419C	ADJUSTABLE EYEBALLS
2	SUCTION OUTLET	ASA	FPK-50-809	9x9 SUCTION OUTLET WITH 3" PORT
2	*MAIN DRAIN COVERS	*AQUASTAR	914101	9x9 ANTI-ENTRAPMENT FRAME & GRATE COVER (394 GPM MAX. RATING)
1	RELIEF VALVE	HAYWARD	SP-1056	1 1/2" HYDROSTATIC RELIEF VALVE
1	COLLECTOR TUBE	HAYWARD	SP-1055	1-1/2" x 12" COLLECTOR TUBE
1	AUTO FILL	PENTAIR	T40FW	AUTOFILL W/ BRASS FLOAT VALVE
1	HANDRAIL	S.R. SMITH	3HR-4-065	4'-0" STAINLESS STEEL HANDRAIL
1	LADDER	S.R. SMITH	VLLS-103S-MG	3-STEP LADDER
1	LIGHT	PENTAIR	78458100	500W INCANDESCENT UNDERWATER LIGHT (50 FT CORD)
1	NICHE	PENTAIR	78210600	STAINLESS STEEL W/ 1" HUB
1	LIFT	AQUA CREEK	RANGER	ADA COMPLIANT HANDICAP SWIM LIFT BATTERY POWERED 350 LB. OPERATING LOAD CAPACITY

*MAIN DRAINS MUST CONFORM TO ANSI/ASME A112.19.8-2007

FILTER

Filter (sand, DE, cartridge) sized properly per .2519 Ref NSF.org

High Rate Sand	15 – 20 gpm per sf of filter surface area
Rapid Rate Sand	3 gpm per sf of filter surface area
Vacuum Sand	15 gpm per sf of filter surface area
DE with slurry	2.5 gpm per sf of filter surface area
DE without slurry	2 gpm per sf of filter surface area
Cartridge	.375 gpm per sf of filter surface area

Filter Mfg. & Model# _____

Number of Filters: _____

Design Flow Rate Ref # 6 ÷ FMR listed in chart = size filter surface area required. Compare to the filter specification sheet for verification that filter surface area is adequate. Filter must handle more than the design flow rate or more filters will be needed.

MFG. & Model # Pentair TR50 _____ Number of Filters 1

$32/20=1.85$ Filter Surface Area on Spec Sheet 2.46

Filter media rates are found in rule .2519. High-rate sand filters are sized at 15 – 20 gpm flow (per mfg) to determine how much square footage of filter surface is required.


Filter Spec Sheet

TRITON® II FIBERGLASS SAND FILTER

Easy access, heavy-duty closure with built-in pressure relief valve makes inspection and maintenance fast, safer and easy

Threaded bulkhead connectors for easy installation and service

Glaslok™ process creates a one-piece, fiberglass-reinforced tank with UV-resistant surface finish for years of unequaled strength and durability



Model Number	Filter Area Sq. Ft	Vertical* Clearance	Filter Diameter	Required Sand† (lbs)	Flow Rate GPM		Turnover Capacity-Res. (Gallons)		
					Res.**	Com.	8 hrs.	10 hrs.	12 hrs.
TR 40	1.92	32.5"	19"	175	38	38	18,240	22,800	27,360
TR 50	2.46	36.75"	21"	225	49	49	23,520	29,400	35,280
TR 60	3.14	37.5"	24"	325	63	63	30,240	37,800	45,360
TR 100	4.91	41.75"	30"	600	98	74	47,040	58,800	70,560
TR 140	7.06	47.25"	36"	925	141	106	67,680	84,600	101,520

†Use standard #20 silica sand.

*Required clearance to remove the closure.

**Maximum flow rate. Flow rate is based on 20 GPM per sq. ft. of filter area. Actual system flow will depend on plumbing size and other system components.

AVAILABLE FROM:



WATER SOLUTIONS, 1620 HAWKINS AVE, SANFORD, NC 27330 800.831.7133 WWW.PENTAIRPOOL.COM

All Pentair trademarks and logos are owned by Pentair, Inc. Triton® and Glaslok™ are trademarks and/or registered trademarks of Pentair Water Pool and Spa, Inc. and/or its affiliated companies in the United States and/or other countries. Because we are continuously improving our products and services, Pentair reserves the right to change specifications without prior notice. Pentair is an equal opportunity employer.

pumps / filters / heaters / heat pumps / automation / lighting / cleaners / sanitizers / water features / maintenance products

6/12 Part # P1-001 ©2012 Pentair Aquatic Systems. All rights reserved. (NSF)



9. Surface Overflow systems:

Number of NSF skimmers required: _____, Plan shows _____

Skimmer Notes:

- Pool surface area (Ref #3) ÷ 400sf or fraction thereof for swimming pools,
- Where flooded suction on the pump is not possible to prevent cavitation or loss of prime, skimmers shall be protected from air entrapment by auto-fill, fill spout/ hose. Equalizer lines are now prohibited in public pools.

Skimmer Mfg. Aquastar & Model # SKR101

Max flow for Skimmer provided per NSF Listing. 55 GPM;
may require additional skimmers if inadequate.


$346 \text{ SF} \div 400 \text{ SF} = 0.87$, round up to 1 Skimmer

The Pool Equipment List SP-2 and SP1 show 1 Skimmer

Skimmer listed on equipment list on SP2

POOL EQUIPMENT LIST				
QTY.	ITEM	MANUFACTURER	MODEL #	DESCRIPTION
1	PUMP	PENTAIR	WFE-2	1/2 HP WHISPER FLO COMMERCIAL PUMP (1 PHASE PUMP)
1	BASKET	PENTAIR	070387	EXTRA STAINER BASKET
1	FILTER	PENTAIR	TR50	NSF APPROVED WITH AIR RELIEF PRESSURE GAUGE
1	VALVE	PENTAIR	261055	MULTIPORT VALVE
1	FLOWMETER	FLOW VIS	FV-C	2" PVC MOUNT (BACKWASH NOT TO EXCEED 50 GPM)
1	CHLORINATOR	PENTAIR	320	AUTOMATIC EROSION TYPE (PENTAIR #171096)
1	SKIMMER	AQUASTAR	SKR101	INCLUDES BASKET
4	RETURN INLETS	HAYWARD	SP-1419C	ADJUSTABLE EYEBALLS
2	SUCTION OUTLET	ASA	FPK-50-809	9x9 SUCTION OUTLET WITH 3" PORT
2	*MAIN DRAIN COVERS	*AQUASTAR	914101	9x9 ANTI-ENTRAPMENT FRAME & GRATE COVER (394 GPM MAX. RATING)
1	RELIEF VALVE	HAYWARD	SP-1056	1 1/2" HYDROSTATIC RELIEF VALVE
1	COLLECTOR TUBE	HAYWARD	SP-1055	1-1/2" x 12" COLLECTOR TUBE
1	AUTO FILL	PENTAIR	T40FW	AUTOFILL W/ BRASS FLOAT VALVE
1	HANDRAIL	S.R. SMITH	3HR-4-065	4'-0" STAINLESS STEEL HANDRAIL
1	LADDER	S.R. SMITH	VLLS-103S-MG	3-STEP LADDER
1	LIGHT	PENTAIR	78458100	500W INCANDESCENT UNDERWATER LIGHT (50 FT CORD)
1	NICHE	PENTAIR	78210600	STAINLESS STEEL W/ 1" HUB
1	LIFT	AQUA CREEK	RANGER	ADA COMPLIANT HANDICAP SWIM LIFT BATTERY POWERED 350 LB. OPERATING LOAD CAPACITY


*MAIN DRAINS MUST CONFORM TO ANSI/ASME A112.19.8-2007



*MUST MEET CURRENT LAWS




5 SKIMMER DETAIL
SP2 SCALE: N.T.S.

Only 1 Skimmer is required per 400 SF surface area



4 POOL PLUMBING PLAN
SP1 SCALE: 1/4" = 1'-0"

SP1

LEGEND	
	RETURN
	SKIMMER
	MAIN DRAIN



Also under 9, gutter system and or Balance Tank.

Doesn't apply to the plan, because this pool is using a skimmer rather than gutter system and there is no balance surge tank.



10. Circulation Main Drains and pipe size:

PVC Sch. 40 Pipe Sizing Chart per .2518©							
pipe size	1"	1.5"	2"	2.5"	3"	4"	6"
Suction PVC pipe @6ft/sec (all drains, skimmers, gutters)	16	38	62	89	138	238	539
Discharge or Returns (inlets) PVC pipe @10ft/sec	27	63	104	149	230	396	899

Number of drains provided: _____

- in deepest section
- within 15 ft. from a side wall.
- connected by T pipe at least 3' apart at center or on different planes of pool
- max 30' apart
- Meets APSP-7
- If no drains provided, provisions for emptying pool completely provided per .2518(j)(1) N/A.

**Are all
of these
criteria
met?**

Main drain pipe size required using pipe sizing chart above: _____" , Plan shows _____"

(Ref #6) , What is our design flow?


- Pipe size must be capable of carrying 100% design flow of circulation pump per .2518(d)

Number of main drains provided: 2

Main drain pipe size required using pipe sizing chart: 1.5" based on 32 GPM design flow.

Plan Shows: 2"

POOL PLUMBING PLAN SP1 showing main drain plumbing 2" suction PVC



$\frac{1}{4}" = 1'$ scale

4 POOL PLUMBING PLAN
SP1 SCALE: $\frac{1}{4}" = 1'-0"$




11. Max flow of circulation pump _____ GPM

Note:

- Use lowest TDH on circulation pump performance curve OR engineer calculated TDH.
- If multi-speed or variable speed pump is provided, use Max flow of highest speed for drain cover comparison in #18.) **REF #7**

Max flow of circulation pump is 90 GPM

Performance Curves





12. Max flow rating of main drain covers _____ max GPM per floor/ wall

- Life span of cover _____ years:
- Cover Mfg. & Model # _____
- **Cover GPM rating must be higher than max flow of pump.**

VGB main drain covers 560/300 max GPM per floor/ wall

Life span of cover 5 years:

Cover Mfg. & Model # Aquastar 914101

Are covers rated higher than the max flow of the pump? YES

560 GPM is greater than max flow 90 GPM of circulation pump.



General Certificate of Conformity (GCC)

14" Square Anti-Entrapment Suction Outlet Cover

Manufacturer:
AquaStar Pool Products, Inc.
2340 Palma Dr. #104
Ventura, CA 93003

Part Number Part #: 914xxx
Flow Ratings: Floor - 560 GPM Wall - 300 GPM
Minimum Sump Depth: 3 inches



This is to certify that this model number meets or exceeds the requirements of Section 1404 (b) of the Virginia Graeme Baker Pool & Spa Safety Act (VGB-2008), ASME/ANSI A112.19.8-2007, ANSI/APSP-16-2011 standards and safety regulation 16 CFR 1450 Virginia Graeme Baker Pool and Spa Safety Act Regulations set forth by the Consumer Product Safety Commission.

Citation: This SOFA is certified to 16 CFR 1450; Virginia Graeme Baker Pool and Spa Safety Act. This product's certification is based upon the International Association of Plumbing and Mechanical Officials test report dated May 25th, 2011 and the certification is renewed annually through continuous compliance inspections by the International Association of Plumbing and Mechanical Officials (IAPMO), 5001 East Philadelphia St Ontario, CA 91761-2816, (909) 472-4100.

The test results supporting the product certification is maintained by Steve Ohnemus 2340 Palma Dr. #104 Ventura, CA 93003, Phone: (877) 768-2717x5021, Email: SteveO@aquastarpoolproducts.com.

Installation Record

Date of Manufacture: _____



The date of manufacture is represented by a time stamp located on the product. Do not use this date to determine the expiration date.

Description of Drain Location: _____

Date Installed: _____
(With or without water in pool or spa)

Expiration Date: _____
(Five years from installation)

Installed by: _____



(877) 768-2717 - www.aquastarpoolproducts.com - info@aquastarpoolproducts.com



13. Main drain sump requirements

(Use VGB drain cover Manufacturer Installation Instructions provided for single or double drain cover to see recommended mfg. sump(s) OR field-built requirements per .2518(j)(3) and .2539(c)(3)(Per APSP – 16, page 4)


FIELD BUILT SUMPS MUST BE CERTIFIED BY A REGISTERED DESIGN PROFESSIONAL OR ENGINEER per APSP 7, page 4

Manufactured Sump	OR minimum Field Built Sump Measurements
Model #	Letter from Registered Design Professional certifying sump is to be built per requirements.

Hydrostatic Relief Valve or Drainage Provided per .2515 (b). Manufacturer and Model# _____

**Aquastar 914101 requires a minimum of 3” sump depth to pipe.
Does the plan show if this is met? NO, “NTS”, means Not To Scale.
But the suction outlet specification sheet that this cover is a compatible grate.**

Hydrostatic Relief Valve? YES, Manufacturer and Model: Hayward SP-1056



MAIN DRAIN DETAIL

SCALE: N.T.S.



The ASME A12.19.8a-2008 Standard recommends the "E" dimension to be 1.5 times the diameter of the sump's outlet from the bottom of the grate to the top of the outlet.



Frame & Grates Sold Separately

Fiberglass LEGACY SUMP Dimensions									
Sump Sizes & Part #'s	Dimensions (in inches) *						Outlet Size f.p.t. x soc	Compatible Grates **	NOTES
	A	B	C	D	E	F			
9" x 9"									
FPK-50-809	10.5	8.5	12	4.5	6.5	3	3"	List A	I
12" x 12"									
FPK-50-812-4	14	12.5	12	4.5	6.5	3.5	4"	List B	I

VGB Compatible Grates *			
Grate Sizes Part #'s	Open Area List (sq in.)**	Flow Rate** @ 1.5 ft/ sec	NOTES
9" x 9" A			
CMP 25508-090	38.9	120 gpm	
640-479XV	39.9	186 gpm	
MLD-FGD-0909	42.1	248 gpm	
914101	84	394 gpm	
12" x 12" B			
WGI032HF	41.07	232 gpm	
640-4720	62.4	292 gpm	
CMP 25508-120	70.8	330 gpm	
MLD-FGD-1212	81.3	340 gpm	

Hydrostatic Relief Valve?

POOL EQUIPMENT LIST				
QTY.	ITEM	MANUFACTURER	MODEL #	DESCRIPTION
1	PUMP	PENTAIR	WFE-2	1/2 HP WHISPER FLO COMMERCIAL PUMP (1 PHASE PUMP)
1	BASKET	PENTAIR	070387	EXTRA STAINER BASKET
1	FILTER	PENTAIR	TR50	NSF APPROVED WITH AIR RELIEF PRESSURE GAUGE
1	VALVE	PENTAIR	261055	MULTIPORT VALVE
1	FLOWMETER	FLOW VIS	FV-C	2" PVC MOUNT (BACKWASH NOT TO EXCEED 50 GPM)
1	CHLORINATOR	PENTAIR	320	AUTOMATIC EROSION TYPE (PENTAIR #171096)
1	SKIMMER	AQUASTAR	SKR101	INCLUDES BASKET
4	RETURN INLETS	HAYWARD	SP-1419C	ADJUSTABLE EYEBALLS
2	SUCTION OUTLET	ASA	FPK-50-809	9x9 SUCTION OUTLET WITH 3" PORT
2	*MAIN DRAIN COVERS	*AQUASTAR	914101	9x9 ANTI-ENTRAPMENT FRAME & GRATE COVER (394 GPM MAX. RATING)
1	RELIEF VALVE	HAYWARD	SP-1056	1 1/2" HYDROSTATIC RELIEF VALVE
1	COLLECTOR TUBE	HAYWARD	SP-1055	1-1/2" x 12" COLLECTOR TUBE
1	AUTO FILL	PENTAIR	T40FW	AUTOFILL W/ BRASS FLOAT VALVE
1	HANDRAIL	S.R. SMITH	3HR-4-065	4'-0" STAINLESS STEEL HANDRAIL
1	LADDER	S.R. SMITH	VLLS-103S-MG	3-STEP LADDER
1	LIGHT	PENTAIR	78458100	500W INCANDESCENT UNDERWATER LIGHT (50 FT CORD)
1	NICHE	PENTAIR	78210600	STAINLESS STEEL W/ 1" HUB
1	LIFT	AQUA CREEK	RANGER	ADA COMPLIANT HANDICAP SWIM LIFT BATTERY POWERED 350 LB. OPERATING LOAD CAPACITY

*MAIN DRAINS MUST CONFORM TO ANSI/ASME A112.19.8-2007

Hydrostatic Valve
SP1056



14. Skimmers pipe size required _____" Plan shows _____"

Note:

- Pipe must handle 100% of design flow rate (Ref #6), which is 37 GPM.
- Skimmer equalizer lines are prohibited in new construction.
- Is autofill/ flooded suction provided _____. Auto-fill mfg # _____


PVC Sch. 40 Pipe Sizing Chart per .2518(c)							
pipe size	1"	1.5"	2"	2.5"	3"	4"	6"
Suction PVC pipe @6ft/sec (all drains, skimmers, gutters)	16	38	62	89	138	238	539
Discharge or Returns (inlets) PVC pipe @10ft/sec	27	63	104	149	230	396	899



Pipe Size Required 1.5" Plan Shows 2" (SP1)

Yes/ Pentair T40FW Autofill W/Brass Float Valve (Pool Equipment List)

Pool Plumbing Plan on SP1



4 POOL PLUMBING PLAN
SP1 SCALE 1/4" = 1'-0"



Or gutter system overflow pipe size _____ "Plan shows _____"

- Must handle 100% of design flow per .2518(j)(3)) (Ref #6) Use chart below.

N/A for this pool because it is designed with recessed automatic skimming rather than gutters.

15. Inlet return pipe size required _____" , Plan shows _____"

- Use *Discharge* pipe sizing chart.
- Must handle 100% design flow of discharge (Ref #6) per .2518(d) and reduction in pipe branches must be sized to handle flow of inlets in each branch.


PVC Sch. 40 Pipe Sizing Chart per .2518(c)							
pipe size	1"	1.5"	2"	2.5"	3"	4"	6"
Suction PVC pipe @6ft/sec (all drains, skimmers, gutters)	16	38	62	89	138	238	539
Discharge or Returns (inlets) PVC pipe @10ft/sec	27	63	104	149	230	396	899



Based on chart, the pipe size required is at least 1.5"

What does the plan show? 2"

4 inlets discharge
through a 2" return loop





16. Disinfectant Method: (Erosion, salt or liquid)

Verify NSF & properly sized per volume of pool: _____

Ref. NSF.org Mfg. & Model # _____

Note:

- If erosion feeder, properly sized and additional flow meter shown if required by NSF Std. 50
- If salt system, cell capacity/ # cells: Per NSF Std. 50 annex must produce 3 lb/day/10,000 gallons. If for water conditioning only, no sizing required, but must have other approved disinfectant system
- If liquid chlorine pump, a method to prevent operation when no water circulation pump operating per .2535(6) (aka Interlock)

**PENTAIR**

AUTOMATIC CHLORINE/BROMINE* FEEDER

MODEL #320

Features:

- No special venting required.
- Completely enclosed-no escaping gases.
- Positive external no-clog control valve.
- When used with timer, feeder is designed to automatically lower the water level so tablets are not soaking during off period of pump. This allows more efficient use of tablets.

(* Using Bromine tablets with this device is not NSF certified)

- No equipment damage.
Feeds sanitizer directly to pool or spa.
- All parts replaceable.
- To prevent over chlorination during use, completely close the control valve and the built in check valve will prevent chemical from being fed into pool or spa.

YOUR FEEDER IS THE MOST EFFICIENT AND TROUBLE-FREE AUTOMATIC FEEDER YOU CAN BUY, BUT IT CAN ALSO BE DANGEROUS TO YOU AND YOUR EQUIPMENT. PLEASE FOLLOW INSTRUCTIONS EXACTLY AND HEED ALL CAUTIONS. YOUR SAFETY AND THE PROTECTION OF YOUR EQUIPMENT IS OUR FIRST CONCERN.

It is important to read all information **BEFORE** proceeding with the installation. The information will guide you in installing your feeder properly and to avoid problems due to improper installation.

IF YOUR POOL OR SPA HAS COPPER PLUMBING . . . STOP!!

Never install the feeder into copper plumbing as pipe damage will occur. (See Equipment Safety CAUTION sheet enclosed). **NOTE:** If heaters are used, a Fireman's Switch or equivalent must be installed to prevent possible damage and improper operation of Check Valve and other equipment subject to heat damage.

INSTALLATION INSTRUCTIONS MODEL #320

Note: Make sure all pumps and timer switches are in the OFF position.

WHERE TO INSTALL YOUR FEEDER

The #320 feeder is designed for permanent installation in the return line of your new pool or spa and must always be installed after the heater, pool cleaner, valves, etc. If your pool does not have a heater, then it must be installed after the filter or any other piece of equipment.

DAMAGE TO THE HEATER AND OTHER EQUIPMENT COULD RESULT IF HIGHLY CHLORINATED WATER FLOWS THROUGH IT.

If your pool is equipped with a solar system it may be necessary to install a **HI FLOW KIT**. This kit can be installed if your feeder is not getting adequate flow and/or pressure through the system. Refer to information on sheet enclosed. Your feeder may be installed in existing PVC plumbing but will require a union and/or other fittings. The feeder comes complete for installation with 2" or 1½" PVC plumbing. Choose a site in the return line where feeder can be installed in a vertical position. Always install as far from any metal equipment as practical since fumes, etc. can corrode them. If optional corrosion resistant check valve is required refer to installation instructions before next step.

BASIC PLUMBING INSTALLATION INSTRUCTIONS

2" OR 1½" PVC PIPE: If feeder is being installed on a pool, spa or pool/spa combination, correct plumbing procedures must be followed to insure proper flow through feeder. If pool or spa is plumbed with 2" PVC pipe, be certain the pump, filter and heater all have 2" inlet and outlet fittings. If any part of the equipment has less than 2" fittings or pipe, then a minimum of 6" x 1½" reducer bushings must be installed directly into the inlet side of the feeder using the 2" x 1½" reducer bushings supplied. This will build pressure directly into the feeder insuring proper operation. Continue with 2" PVC pipe on the outlet side of the feeder.

POOL/SPA COMBINATION: If plumbing and equipment is a full 2" and the feeder is being installed on the pool return line after the diverter valve, with a portion of the water diverted to the spa, install a minimum section of 6" x 1½" PVC pipe directly into the inlet side of the feeder using the 2" x 1½" reducer bushing supplied. Continue with 2" PVC pipe on the outlet side of the feeder. This will compensate for that portion of water being diverted to the spa.

90° ELBOWS: Plumbing a 90° elbow directly into the inlet side of the feeder may cause turbulence inside the elbow. This will prevent water from being scooped into the feeder. A minimum of a 6" length of PVC pipe should be installed between the 90° elbow and the inlet side of the feeder.

chemical residual. It is recommended that the chemical residual be checked daily for the first 5 days. Remember . . . hot days, higher water temperature or increased pool/spa activity will cause your pool/spa to use more sanitizer. When possible, increase the feed rate a day or two in advance. Because the chlorine demand in your pool/spa varies and is dependent on many factors (sunlight, bather load, water temperature, etc) your valve setting may have to be changed from time to time to adjust to these conditions. For example, the winter setting may be #2 while the summer setting is #3. Check the chlorine residual daily to find the ideal setting. Note: Higher numbers dispense more chemical. Small gradual changes are imperative for control.

HOW TO RECHARGE FEEDER

1. Turn control valve to the closed position. **SHUT OFF PUMP.**
2. Wait one minute. This will allow water and fumes to drain from feeder.
3. Leave control valve closed and turn on pump. The check valve will prevent water from entering the feeder.
4. Remove cap and fill with proper size tablets or sticks. (See Operating Instructions #1)
5. Making sure O-ring is clean, lubricated with Lifeguard silicone and is in place, replace cap. Hand tighten only.
6. Open control valve to original setting. Inspect inlet line below control valve each time feeder is recharged. Replace lines yearly if necessary.


SPECIAL FEATURES AND INSTRUCTIONS

If while using 3" diameter tablets the #320 feeder does not provide enough chlorine residual, switch to 1" tablets. The smaller tablet will erode faster producing more chlorine residual. If this does not correct the situation, the #320 has been fitted with an optional opening at the top of the feeder (which is plugged). To accommodate attachment of the valve and tubing assembly for top entry of water into the feeder, an additional length of tubing has been included. The following procedure should only be used if the suggested change has not solved the situation. Top entry in normal situations can cause over chlorination.

1. Turn off pump and timer switches.
2. Remove tubing by unscrewing compression nut at each end of tubing.
3. Remove plug at top of feeder directly above control valve.
4. Remove control valve. If nipple stays in valve, carefully remove by using pliers at the center of nipple. There is no need to remove the 90° tube fittings.
5. Wrap plug with 2 or 3 wraps of threaded tape in opposite direction of tightening. Screw into opening where control valve was attached. Hand tighten plus 2 or 3 turns. Do not overtighten.
6. Wrap threads of nipple with threaded tape. Thread nipple into top opening. Finger tighten only. Thread valve onto nipple. After nipple starts to turn from tightening valve, 2 to 3 more turns is enough. The nipple or valve can be broken by overtightening.
7. Slide compression nut over long section of tube. Slide tube over tapered part of 90° tube fitting and tighten. Hand tighten only. Repeat for other end of tubing.
8. Set control valve to #1. Turn on pump and timers. Check residual daily to determine proper setting. Small gradual changes are imperative for control.

HI FLO FEEDER KIT #R171099 PARTS BREAKDOWN DRAWING

Item	Quantity	Part No.	Description
1	1	R172134	Plug, 1/2" MPT
2	6 ^{ft}	R172093	Tube, 1/2" ID Chlorinator
3	1	R175013	Clamp, S.S. Tubing
4	1	R171162	Fitting, Saddle Tube
5	1	R172263	Gasket, Saddle
6	1	R172264	Clamp, Saddle
7	1	R172324	Valve, 1/2" Tube check






17. Vacuum cleaning system provided per .2518(f)

- Note:
- Vacuum ports located on pool wall 6"-<18" below water level. Skimmer vacuums may be used in pools with ≤ 2 skimmers and negate need for separate vacuum port.
- Vacuum piping, if separate from skimmer operation may be suction or discharge and should be sized according to manufacturer's requirements.
- Specifics not mentioned in rules.
- Self-closing caps requiring tools to open per .2518 (f)

Port vacuum cover Mfg. _____

Model# _____

Note: no vacuum line shown on plumbing plan



4 POOL PLUMBING PLAN
 SP1 SCALE: 1/4" = 1'-0"

Vacuum line not shown
 so CPO will vacuum
 through the skimmer.


CLEANING AND SAFETY EQUIPMENT

QTY.	ITEM	MANUFACTURER	MODEL #	DESCRIPTION
1	VACUUM HEAD	PENTAIR	R201126	19 IN. FLEXIBLE VACUUM HEAD
1	WALL BRUSH	PENTAIR	R111316	18 IN. WHITE POLYPROPYLENE
1	LEAF SKIMMER	PENTAIR	R121196	HEAVY DUTY SKIMMER
1	ADJUSTABLE POLE	PENTAIR	R500070	8'-16' ADJUSTABLE POLE
1	LIFE HOOK	PENTAIR	R221026	ALUMINUM HOOK WITH HARDWARE SET
1	UTILITY POLE	PENTAIR	R191106	12' STRAIGHT POLE
1	VACUUM HOSE	ACTION/HAVILAND	NA225	1-1/2" x 50 FEET
1	LIFE RING	CAL-JUNE	GW-24	20" USCG APPROVED
1	THROW LINE	AJ GIAMMANCO	#60	1/4" x 50 FEET
1	TEST KIT	PENTAIR	R151716	PROFESSIONAL TEST LAB
2	SIGNS	PENTAIR	R234000	N.C. POOL RULES SIGN
4	SIGNS	PENTAIR	R231200	NO DIVING ALLOWED
2	SIGN	HAE	SBE	SHOWER BEFORE ENTERING
4	SIGN	PENTAIR	R230500	NO LIFEGUARD ON DUTY
2	SIGN	-	-	NO NIGHT SWIMMING
2	SIGN	-	R231700	EMERGENCY TELEPHONE SIGN

18. Valves provided to control flow from drains, surface skimmers or surface overflow systems, and vacuuming cleaning system .2518 (c) and (f)


POOL EQUIPMENT LIST				
QTY.	ITEM	MANUFACTURER	MODEL #	DESCRIPTION
1	PUMP	PENTAIR	WFE-2	1/2 HP WHISPER FLO COMMERCIAL PUMP (1 PHASE PUMP)
1	BASKET	PENTAIR	070387	EXTRA STAINER BASKET
1	FILTER	PENTAIR	TR50	NSF APPROVED WITH AIR RELIEF PRESSURE GAUGE
1	VALVE	PENTAIR	261055	MULTIPORT VALVE
1	FLOWMETER	FLOW VIS	FV-C	2" PVC MOUNT (BACKWASH NOT TO EXCEED 50 GPM)
1	CHLORINATOR	PENTAIR	320	AUTOMATIC EROSION TYPE (PENTAIR #171096)


Valves on each suction and return line plus a multi-port valve required.



3 POOL EQUIPMENT ROOM
SP1 SCALE: 3/8" = 1'-0"

19. Drainage discharged through air gap from pool overflow, deck drains and filter backwash per .2513(b)





3 POOL EQUIPMENT ROOM
 SP1 SCALE: 3/8" = 1'-0"




20. If lighting is provided: 0.5 watts per SF of pool surface (or lumens as required in rule .2524(d).

Nighttime swimming must meet Session Law 2017-209 and requires a nighttime visit by EHS.

Pool plan shows 500-watt light

350 sq. ft. x 0.5 = 175 watts required, lighting on plan exceeds requirement.

20. Pool Lights



UNDERWATER LIGHT DETAIL

SCALE: N.T.S.

21.

Minimum deck width required _____ ft. per .2522 (a) – © & (i) **(Ref #3)**


Minimum Deck Requirements

	Outdoor Pool	Indoor Pool	Wading Pool	Spa	Interactive Play	Permanent Structure
Deck Clearance	< 1600 sf = 6 ft > 1600sf = 8 ft	5 ft	4 ft	4 ft at least ½ around	Not Required	5 ft around diving board, handrail, slide, or other permanent structure
Vertical Clearance	NA	7 ft	7 ft	7 ft	Not Required	13 ft above board See Rule .2517

.2522 (a-e, i), .2543 (10), Special purpose pools such as waterslides and wave pools may vary from the minimum requirements to accommodate feat ADA Chairs – NC Building Code enforced. New constructed pools over 300' perimeter may be required 2 access entries (lift and ramp). Lifts are per infringe on pool decks but cannot block emergency egress corridors required for fire safety. Deck slope to drain ¼ to ½"/ft; slip resistant.

Minimum deck width required is 6 FT. because pool surface area is < 1600 sf

SP1 shows sufficient deck space




**Measure Deck Space on SP1
and A5.o8 which shows
furniture - next slide**

SCALE: 3" = 1'-0"

"NO DIVING" AND DEPTH MARKER TILES LOCATED AT EACH ADDITIONAL CHANGE IN FEET OF DEPTH. MARKER TILES MUST HAVE A MINIMUM LETTERING SIZE OF 4" AND INDICATE DEPTH IN FEET AND METERS. SEE DESIGN STANDARDS.

SCALE: 1/2" = 1'-0"

PROVIDE 5'-0"
LANDSCAPE BUFFER
ON THIS SIDE





22. Ladders, steps, stairs, handrails required _____, Plan shows _____

Notes:

- If >2' deep, 1 in shallow; 1 in shallow & deepest, every 75'.
- If pool width > 30 ft, 2 ladders are required on either side of the deep end.
- Total # of Ladders/ Handrails Required = Perimeter ÷ 75 ft along *shallow* (5' depth of perimeter. Subtract one if steps present in shallow end)

Need 1 in shallow and 1 in deep


SP1 show a set of stairs in the shallow end and a ladder in the deep end

Ladder and stairwell

ADA HANDICAP LIFT
SEE DETAIL 1/SP2

ANCHORS GROUNDED
TO STEEL REINFORCING
FOR RAILS (TYP.)

25'-0"



500 WATT UNI
LIGHT (1 REQ
NICHE BONDED
STEEL REINFO
GROUND WIRE
WITH UL LISTE
POTTING COMF

9x9 MAIN DRAINS
(DRAIN COVER
MAX. RATING 394 GPM)


WALL RETURN
INLET

3'0"
DEEP

5'0"
DEEP

A
SP2

A
SP2



2x2 NON SKID COLOR
CONTRASTING TILE
◎ STEP EDGE

SEE DETAIL
2/SP1(TYP.)

POOL BONDING
SEE DETAIL 2/SP2

SKIMMER

AUTOFILL
WATER SUPPLY
BY OWNER

6'-8"

9'-7"
14'-0"

R2'-1"

R2'-1"

23. Pool bather load _____ (Pool surface area (Ref #3) ÷ applicable # in chart below and round down)

POOL DEPTH(s) _____

Portion of Pools <5 ft	15sf/person per .2529(1)
Portion of Pools >5 ft (-300sqft at diving boards)	24sf/person per .2529(2)
Spas, wading pools, CAP	10sf/person per .2529(3) &.2531(a)(8)
Interactive play attraction splash zone	25sf/person per .2529(4)

346sf/15sf per person = 23 people

Pool Specifications shows bather load is 23 persons on SP1

POOL SPECIFICATIONS

- WATER SURFACE AREA IS 346 SQ. FT.
- WATER DEPTH IS 3'-0" TO 5'-0"
- NET CAPACITY IS 10,366 GALLONS WITH A FILTRATION CYCLE OF 5 HOURS AND 24 MIN AT A FLOW OF 32 GPM. (BASED ON A DYNAMIC HEAD OF 65 FEET)
- POOL PERIMETER = 74.5 LN. FT
- ALL PIPE WORK SHALL BE SCHEDULE 40 PVC, PRESSURE TESTED BEFORE PLACING CONCRETE
- -BATHER LOAD IS 23 PERSONS
AS PER GS 15A:18A SECTION 2529
- DECK AREA = 1,787 SQ. FT. BY OTHER THAN SPC

Found on page SP1

24. **Restroom fixtures based on bather load.** (.2526) Use chart for bath houses for male/female facilities. At hotel, motel, condo or apartment complex where the farthest unit is more than 300' from the pool as measured along walkways, only a toilet and lavatory are required.

Divide Ref #12 equally between men and women.

Men	Toilet	Lavatory	Urinal	Showers	Women	Toilet	Lavatory	Showers
0-50	1	1	0	1	0-50	1	1	1
51-100	1	1	1	1	51-100	2	2	1
101-200	2	2	2	1	101-200	3	3	1
201-300	2	2	2	2	201-300	4	4	2
301-400	3	3	3	2	301-400	5	5	2
401-500	3	3	3	3	401-500	6	6	3
501-750	5	5	5	3	501-750	8	7	3

*If rinse showers are located on pool deck, 1 per every 200 bathers

*Shower drains are enforced by the building codes department. Typically, showers in bathhouses drain to sewer and cold-water showers on pool decks drain to the deck drains.

With a bather load of 23, 1 toilet 1 lavatory and 1 shower would be required for both men and women.

Bathroom facilities

GENERAL NOTES

- * FLOOR DRAIN, BACKWASH SUMP, APPROVED MUNICIPAL WATER SUPPLY, CONCRETE DECK AND ELECTRICAL SHALL BE PROVIDED BY THE GENERAL CONTRACTOR AND OR OWNER.
- * CHEMICAL STORAGE ROOM MUST BE PROVIDED TO MEET STATE REGULATIONS IN DETAILED SPECIFICATIONS.
- * A HOSE BIB WITHIN 100' OF ALL DECK AREAS SHALL BE PROVIDED BY OTHERS.
- * ALL SIGNAGE TO MEET N.C. G.S. WILL BE PROVIDED.
- * SAFETY EQUIPMENT WILL BE STORED ON FENCE.
- * POOL SUPPLY WATER WILL BE SUPPLIED THROUGH AN AUTOFILL.
- * BATHROOM FACILITIES SHALL HAVE A SLIP RESISTANT FLOOR & HAVE A MIN. OF: MEN'S 1 LAV., AND 1 WATER CLOSET. WOMEN'S 2 LAV'S., 2 WATER CLOSET.
- * EMERGENCY PHONE SHALL BE PROVIDED IN DECK AREA WITHIN 75 FEET OF BATHER ENTRANCE..

1 extra water closet and lavatory for the women's restroom. What about shower?

25. **Chemical storage room** minimum size: _____ sf


Rules require a min 5sf for 10,000 gallons + 1sf for each additional 3000 gallons

(REF #4) PLAN _____ SF

$$\begin{array}{rcl} & 10,366 & \\ - & \underline{10,000 \text{ g}} & 5 \text{ SF} \\ = & 366 \text{ g} & \underline{1 \text{ SF}} \\ & & 6 \text{ SF required minimum chemical storage} \end{array}$$

Plan shows ? SF of chemical storage space.

Use architect's scale
to measure chemical
storage room
dimensions.



3 POOL EQUIPMENT ROOM
SP1 SCALE: 3/8" = 1'-0"



Numbers 26 - 33 on the calculation sheet deal with water features such as deck jets, fountains, and hydrotherapy . None are part of this pool design so these items don't apply.



Questions?